



Pellet Silos

Base Pricing	Excl GST	Incl GST
60D-290	\$5,920	\$6,512
60D-400	\$6,170	\$6,787
60D-500	\$7,010	\$7,711
60D-650	\$7,830	\$8,613
60D-800	\$8,470	\$9,317
60D-1000	\$8,870	\$9,757
60D-1250	\$9,320	\$10,252
60D-1500	\$9,840	\$10,824

Delivery Charges	Excl GST
Truck & Trailer (p/Km One Way)	
• All Silo's	\$4.00
Escort Vehicles Required (p/Km One Way)	
• Silo's over 3.73M (1 Required)	\$2.25
Oversize Permit Charges (Once Off)	
• Silo's over 3.73M	\$120

Optional Extras

Blower Pipes for Elevated Silos	
◦ 60D-290, 400 (4" / 5")	\$450 / \$750
◦ 60D-500, 650, 800 (4" / 5")	\$580 / \$800
◦ 60D-1000, 1250, 1500, 1800 (4"/5")	\$670 / \$970

SPECS	Dia (m)	No Tnk Rng	Cu/m	Height (m)	Aug Ltn (ft)	Aprx Bush	Wheat	Lupin	Size			
									Canola	Barley	Oats	
60D-290	2.5	2	10.45	4.8	28	305	8.6	9	8	7.2	5.8	
60D-400	2.5	3	14.68	5.7	32	423	12.6	12.75	11.4	9.9	7.8	
60D-500	3.1	2	16.85	4.5	27	495	13.9	14.6	12.5	11.3	8.9	
60D-650	3.1	3	23.34	5.4	32	677	19.2	19.8	16.8	15.7	12	
60D-800	3.1	4	29.84	6.3	36	852	24.3	25.2	21.5	20	15.4	
60D-1000	3.76	3	35.66	6.8	39	1026	29.2	30.1	26.3	23.9	18.4	
60D-1250	3.76	4	45.21	7.7	43	1290	37.0	38.5	32.6	30.5	23.4	
60D-1500	3.76	4.5	56.65	8.2	45	1548	44.3	46.1	39.8	36	28	

- All silo's are auger filled
- No deposit if silo can be delivered within 30 days (10% Deposit on other occasions)
- Fully Galvanised
- Fitted with 300mm Whirly Bird ventilators
- Blower pipe fitted upon request
- Non sealed silo's due to high moisture products
- Silo concrete pads to be a maximum of 200mm to top of slab above ground.

DISCLAIMER: Pedericks have made every effort to ensure the information on this page is accurate, however we cannot accept responsibility for any omissions or inadvertent errors. All products remain the property of Pederick Engineering until paid for in full. Minimum delivery of \$300 + GST. + Escort charges Silo Concrete pads are to be a maximum of 200mm above ground level.