



## Grain Silos

- All sealed silos are fitted with fumigation containers and factory tested
- No deposit if silo can be delivered within 30 days (10% Deposit on other occasions)
- Fully Galvanised
- Requires 200mm Concrete pad above ground level.

Base Pricing	Excl GST	Incl GST	Delivery Charges	Excl GST
290	\$4,900	\$5,390	Truck & Trailer (p/Km One Way)	
400	\$5,400	\$5,940	• Silos up to 4.5M	\$4.00
500	\$5,800	\$6,380	• Silos over 4.5M	\$6.00
650	\$6,120	\$6,732	Excort Vehicles Required (p/Km One Way)	
800	\$6,350	\$6,985	• Silo's over 3.73M (1 Required)	\$2.25
1000	\$6,850	\$7,535	• Silos over 4.5M (2 Required)	\$4.50
1250	\$7,200	\$7,920	Oversize Permit Charges (Once Off)	
1500	\$7,880	\$8,668	• Silo's over 3.73M	\$120
1700	\$8,150	\$8,965	<b>Optional Extras</b>	
1900	\$8,700	\$9,570	Blower Pipes for Elevated Silos	
2000	\$8,950	\$9,845	▪ 290, 400 (4" / 5")	\$450 / \$750
2300	\$9,450	\$10,395	▪ 500, 650, 800 (4" / 5")	\$580 / \$800
2400	\$9,700	\$10,670	▪ 1000 - 3000 (4" / 5")	\$670 / \$970
2700	\$10,300	\$11,330	Replacement Silo Relief Valves	\$170
2800	\$11,200	\$12,320	Bag Off Chute	\$370
3000	\$13,150	\$14,465		

SPECS	Size										
	Dia (m)	No Tnk Rng	Cu/m	Height (m)	Aug Ltn (ft)	Aprx Bush	Wheat	Lupin	Canola	Barley	Oats
290	2.5	2	10.45	3.5	18	287	8.03	8.6	7.3	6.8	5.2
400	2.5	3	14.68	4.4	23	403	11.7	12.1	10.2	9.5	7.3
500	3.1	2	16.85	3.8	22	463	13.4	14	11.8	10.9	8.4
650	3.1	3	23.34	4.6	27	642	18.6	19.3	16.3	15.1	11.6
800	3.1	4	29.84	5.5	31	820	23.8	24.7	20.8	19.4	14.9
1000	3.76	3	35.66	5.0	30	981	28.5	29.5	25.6	23.1	17.8
1250	3.76	4	45.21	5.9	34	1243	36.1	37.5	31.6	29.3	22.6
1500	3.76	5	54.76	6.7	40	1506	43.8	45.4	38.3	35.5	27.3
1700	4.3	4	59.98	6.0	35	1650	47.9	49.7	41.9	38.9	30
1900	4.5	4	66.22	6.2	36	1822	53	54.9	46.3	43	33.1
2000	4.3	5	72.47	6.9	40	2000	57.9	60.1	50.7	47.1	36.2
2300	4.5	5	79.91	7.0	40	2197	63.9	66.3	55.9	51.9	40
2400	4.3	6	84.96	7.8	42	2337	67.9	70.5	59.4	55.2	42.4
2700	4.5	6	93.59	7.9	43	2574	74.8	77.6	65.5	60.8	46.7
2800	4.9	5	96.75	7.6	42	2660	77.4	80.3	67.73	62.89	48.38
3000	4.9	6	112.59	8.4	48	3092	90	93.5	78.8	73.1	56.25

DISCLAIMER: Pedericks have made every effort to ensure the information on this page is accurate, however we cannot accept responsibility for any omissions or inadvertent errors. All products remain the property of Pederick Engineering until paid for in full. Minimum delivery of \$300 + GST. Silo Concrete pads are to be a minimum of 200mm above ground level.